

Job No. 254577

Date: 27th July 2015

Groundtrax Systems Ltd Station Yard Ripley Harrogate North Yorkshire HG3 3BA

TESTING OF COMPOSITE RAMP MATERIAL

Test carried out to composite floor matting made up from re-cycled PVC. Test carried out on 03/07/15 on behalf of Groundtrax.

The test piece supplied was placed onto a compression test machine between two pieces of metal plate, one above and one below test piece so load applied was evenly distributed. The depth of the test piece without any load applied measured 75mm. The test carried out was applied in 10T increments – results are as follows:

Original Thickness 75mm

APPLIED I OAD	COMPRESSION RECORDED

10T	72mm	- 2mm	Returned to original
20T	71mm	- 4mm	Returned to original
30T	67mm	- 8mm	Returned to original

No visible cracks or distortion were found on the test piece.

Yours faithfully

For Lloyds British Testing Ltd



Test Engineer











TRADING UNDER LLOYDS BRITISH TESTING LTD